



**India Meteorological Department
(Ministry of Earth Sciences)**

National Bulletin No. 35 (BOB/08/2025)

TIME OF ISSUE: 0220 HOURS IST

DATED: 29.11.2025

FROM: INDIA METEOROLOGICAL DEPARTMENT (FAX NO. 24643965/24699216/24623220)

TO: CONTROL ROOM, NDM, MINISTRY OF HOME AFFAIRS (FAX.NO. 23093750)

CONTROL ROOM NDMA (FAX.NO. 26701729)

CABINET SECRETARIAT (FAX.NO.23012284, 23018638)

PS TO HON'BLE MINISTER FOR S & T AND EARTH SCIENCES (FAX NO.23316745)

SECRETARY, MOES (FAX NO. 24629777)

H.Q. (INTEGRATED DEFENCE STAFF AND CDS) (FAX NO. 23005137/23005147)

DIRECTOR GENERAL, DOORDARSHAN (23385843)

DIRECTOR GENERAL, AIR (23421105, 23421219)

PIB MOES (FAX NO. 23389042)

UNI (FAX NO. 23355841)

D.G. NATIONAL DISASTER RESPONSE FORCE (NDRF) (FAX NO. 26105912, 2436 3260)

DIRECTOR, PUNCTUALITY, INDIAN RAILWAYS (FAX NO. 23388503)

CHIEF SECRETARY, ODISHA (FAX NO. 0674-2536660)

CHIEF SECRETARY, WEST BENGAL (FAX NO. 033-22144328)

CHIEF SECRETARY, ANDAMAN & NICOBAR ISLANDS (FAX NO. 03192-232656)

CHIEF SECRETARY, TAMIL NADU (FAX NO. 044-25672304)

CHIEF SECRETARY, ANDHRA PRADESH (FAX NO. 0863-2441029)

CHIEF SECRETARY, PUDUCHERRY (FAX NO. 0413-2334145)

CHIEF SECRETARY, KERALA (FAX NO. 0471-2327176)

CHIEF SECRETARY, LAKSHADWEEP (FAX NO. 048-96268124)

Subject: Cyclonic Storm Ditwah [Pronunciation: Ditwah] over southwest Bay of Bengal and adjoining North Sri Lanka & Tamil Nadu coasts: Cyclone Warning for north Tamil Nadu & Puducherry and adjoining south Andhra Pradesh coasts (Red Message)

The **Cyclonic Storm Ditwah [Pronunciation: Ditwah]** over southwest Bay of Bengal and adjoining north Sri Lanka & Tamil Nadu coasts moved nearly northwards with the speed of 05 kmph during past 6 hours and lay centered at 2330 hrs IST of yesterday, the 29th November 2025 over southwest Bay of Bengal and adjoining North Tamil Nadu- Puducherry coasts, near latitude 10.7°N and longitude 80.6°E, about 90 km east-northeast of Vedaranniyam (India), 90 km east-southeast of Karaikal (India), 130 km north-northeast of Jaffna (Sri Lanka), 160 km south-southeast of Puducherry (India) and 260 km south of Chennai (India).

It is very likely to move nearly northwards parallel to North Tamil Nadu-Puducherry coasts during next 24 hours. While moving northwards the cyclonic storm will be centered over southwest Bay of Bengal within a minimum distance 50 km and 25 km from the Tamil Nadu-Puducherry coastline by early morning and evening of today, the 30th November respectively.

Forecast track and intensity are given in Table below

29.11.25/2330	10.7/80.6	70-80 gusting to 90	Cyclonic Storm
30.11.25/0530	11.1/80.5	70-80 gusting to 90	Cyclonic Storm
30.11.25/1130	11.6/80.5	65-75 gusting to 85	Cyclonic Storm
30.11.25/1730	12.2/80.5	55-65 gusting to 75	Deep Depression
30.11.25/2330	12.8/80.5	50-60 gusting to 70	Deep Depression
01.12.25/1130	13.8/80.5	45-55 gusting to 65	Depression

(i) Rainfall Warning:

- ❖ **Tamil Nadu & Puducherry:** Light to moderate rainfall at most places with **heavy to very heavy at many places & extremely heavy rainfall (>20 cm) at isolated places** over north coastal Tamil Nadu & Puducherry on 30th November, 2025. Thereafter, rainfall would gradually decrease to light to moderate at many places with **heavy rainfall** at isolated places on 1st December.
- ❖ **Coastal Andhra Pradesh-Yanam & Rayalaseema:** Light to moderate rainfall at most places with **heavy to very heavy at a few places & extremely heavy rainfall (>20 cm) at isolated places on 30th November.** It would then decrease gradually becoming light to moderate rainfall at many places with **heavy rainfall** at isolated places on 1st December.
- ❖ **Kerala & Mahe:** Light to moderate rainfall at many places with **heavy rainfall** at isolated places till 0830 hrs IST on 30th November.
- ❖ **Adjoining Telangana:** Light to moderate rainfall at a few places with **heavy rainfall** at isolated places is very likely on 30th November.

(ii) Wind Warning:

(a) Along & off north Tamil Nadu & Puducherry Coasts

Gale wind speed reaching 70-80 gusting to 90 kmph is likely to prevail till 30th morning. Thereafter it is likely to decrease gradually becoming squally wind speed reaching 45-55 gusting to 65 kmph by 1st December morning.

(b) Southwest Bay of Bengal, Gulf of Mannar, Comorin area and along & off north Sri Lanka coasts

Gale wind speed reaching 70-80 gusting to 90 kmph is prevailing and likely to continue till 30th November morning. Thereafter it is likely to decrease gradually becoming squally wind speed reaching 45-55 gusting to 65 kmph by morning of 1st December.

(c) Along & off south Tamil Nadu coast

Gale wind speed reaching 70-80 gusting to 90 kmph is prevailing and likely to continue till 30th November morning. Thereafter it is likely to decrease gradually becoming squally wind speed reaching 45-55 gusting to 65 kmph by morning of 1st December.

(d) Adjoining Westcentral Bay of Bengal and along & off south Andhra Pradesh coast:

Gale wind speed reaching 60-70 kmph gusting to 80 kmph is likely to prevail till 30th morning. Thereafter, it is likely to decrease becoming squally wind speed reaching 45-55 kmph gusting to 65 kmph on 01st December morning.

(iii) Sea Condition:

(a) Along & off north Tamil Nadu & Puducherry Coasts

Sea condition is very likely to be High till 30th morning. It is very likely to improve gradually becoming very rough to rough on 1st and 2nd December and gradually improve thereafter.

(b) Southwest Bay of Bengal, Gulf of Mannar, Comorin area and along & off Sri Lanka coasts

Sea condition is very likely to be High till 30th November morning. It is very likely to improve gradually becoming very rough to rough by morning of 1st December and gradually improve thereafter.

(c) Along & off south Tamil Nadu coast

Sea condition is very likely to be High till 30th November morning. It is very likely to improve gradually becoming very rough to rough by morning of 1st December and gradually improve thereafter.

(d) Adjoining Westcentral Bay of Bengal and along & off south Andhra Pradesh coast:

Very rough to high sea conditions are very likely till 30th November morning. Thereafter, it is likely to improve gradually becoming very rough to rough on 01st and 2nd December.

(iv) Storm Surge Warning:

Storm surge of height about 0.5 m to 1m above the astronomical tide (0.4 m during high tide) is likely to inundate the low-lying coastal areas of Tamil Nadu- Puducherry till 30th morning.

(v) Fishermen Warning:

(a) Total suspension of fishing operations in coastal areas of Sri Lanka, Tamil Nadu, Puducherry and south Andhra Pradesh coasts till 01st December.

(b) Fishermen are advised not to venture into

- (i) Southwest Bay of Bengal, Gulf of Mannar, Comorin area and along & off Tamil Nadu, Puducherry & Sri Lanka coasts till 01st December.
- (ii) Adjoining areas of westcentral Bay of Bengal and along & off Andhra Pradesh coast till 2nd December.
- (iii) Adjoining areas of Southeast Arabian Sea, Lakshadweep, Maldives and along & off Kerala coast till 30th November.
- (c) Those out at sea should avoid southwest Bay of Bengal, Gulf of Mannar, Comorin area and along & off Tamil Nadu, Puducherry, south Andhra Pradesh & Sri Lanka coasts; adjoining westcentral Bay of Bengal till 01st December and Southeast Arabian Sea, Lakshadweep, Maldives and along & off Kerala coast till 30th November.

(vi) Impact Expected and Action Suggested due to heavy rain and strong winds (Tamil Nadu, Puducherry and south Andhra Pradesh)

Impact Expected

- ❖ Damage to thatched houses. Thatched Roof tops may blow off.
- ❖ Damage to power and communication lines. Damage to electric poles.
- ❖ Breaking of tree branches, uprooting of small trees. Large-scale damage to banana and papaya trees. Dead limbs may blow from trees.
- ❖ Damage to paddy crops, horticultural and standing crops due to inundation & winds. Damage to Kutchra roads and some damage to Pucca roads and culverts.
- ❖ Inundation of low-lying areas in coastal districts due to heavy rainfall and flash flood. Flooding of escape routes.
- ❖ Localized Flooding of roads, water logging in low lying areas. Sub-merging of power-stations.
- ❖ Riverine flooding in some river catchments.
- ❖ Possibility of coastal flooding and coastal erosion is also very likely over coastal districts of Tamil Nadu, Puducherry and south Andhra Pradesh.
- ❖ Occasional reduction in visibility due to heavy rainfall.
- ❖ Disruption of traffic due to water logging and squally/gale winds
- ❖ Localized Landslides/Mudslides.

Action suggested:

- ❖ Total suspension of fishing operations.
- ❖ Coastal hutment dwellers to be moved to safer places. People in affected areas to remain indoors.
- ❖ Take safe shelters; do not take shelter under trees, as there could be lightning.
- ❖ Movement in motor boats unsafe.
- ❖ Judicious regulation of offshore/onshore operations
- ❖ People are advised to keep a watch on the weather for worsening conditions and be ready to move to safer places accordingly.
- ❖ In case of expected lightning, unplug electrical/ electronic appliances, immediately, get out of water bodies and keep away from all the objects that conduct electricity.
- ❖ Tourism and recreational activities to be regulated.
- ❖ Surface transport and helicopter services to be regulated.

Next bulletin will be issued at 0530 hours IST of today, the 30th November, 2025.

(Shashi Kant)
Scientist-D, IMD, New Delhi


*Copy to: ACWC Kolkata/ACWC Chennai/CWC Bhubaneswar/CWC Vishakhapatnam/CWC
Thiruvananthapuram/ Meteorological Centre Vijay Puram/ and Meteorological Centre Amaravati*



INSAT-3DS IMG, Thermal Infrared1 Count @ 10.83 μm
GMT:29-11-2025/(1930-1957) IST:30-11-2025/(0100-0127)
LIC MERCATOR (LINEAR STRETCH: 1%)


509

857





OBSERVED AND FORECAST TRACK OF CYCLONIC STORM "DITWAH" OVER SOUTHWEST BAY OF BENGAL AND ADJOINING NORTH TAMILNADU-PUDUCHERRY COASTS BASED ON 1800 UTC (2330 Hrs. IST) OF 29TH NOVEMBER 2025



DATE/TIME IN UTC

IST=UTC + 0530

L: LOW PRESSURE AREA

WML: WELL MARKED LOW PRESSURE AREA

D: DEPRESSION (17-27 KT)

DD: DEEP DEPRESSION (28-33 KT)

CS: CYCLONIC STORM (34-47 KT)

SCS: SEVERE CYCLONIC STORM (48-63 KT)

VSCS: VERY SEVERE CYCLONIC STORM (64-89 KT)

ESCS: EXTREMELY SEVERE CYCLONIC STORM (90-119 KT)

SuCS: SUPER CYCLONIC STORM (≥ 120 KT)

● LESS THAN 34 KT

○ 34-47 KT

⦿ ≥ 48 KT


— OBSERVED TRACK

— FORECAST TRACK

▲ CONE OF UNCERTAINTY



OBSERVED AND FORECAST TRACK ALONGWITH QUADRANT WIND DISTRIBUTION OF CYCLONIC STORM "DITWAH" OVER SOUTHWEST BAY OF BENGAL AND ADJOINING NORTH TAMILNADU-PUDUCHERRY COASTS BASED ON 1800 UTC (2330 Hrs. IST) OF 29TH NOVEMBER 2025



DATE/TIME IN UTC

IST=UTC + 0530

L: LOW PRESSURE AREA

WML: WELL MARKED LOW PRESSURE AREA

D: DEPRESSION (17-27 KT)

DD: DEEP DEPRESSION (28-33 KT)

CS: CYCLONIC STORM (34-47 KT)

SCS: SEVERE CYCLONIC STORM (48-63KT)

VSCS: VERY SEVERE CYCLONIC STORM (64-89 KT)

ESCS: EXTREMELY SEVERE CYCLONIC STORM (90-119 KT)

SuCS: SUPER CYCLONIC STORM (≥ 120 KT)

● LESS THAN 34 KT

○ 34-47 KT

● ≥ 48 KT

— OBSERVED TRACK

— FORECAST TRACK

— CONE OF UNCERTAINTY

AREA OF MAXIMUM SUSTAINED WIND SPEED:

— 28-33 KT (52-61 KMPH)

— 34-49 KT (62-91 KMPH)


— 50-63 KT (92-117 KMPH)





— ≥ 64 KT (≥118 KMPH)

IMPACT OVER THE SEA

MSW (knot/kmph)	Impact	Action
28-33 (52-61)	Very rough seas	Total suspension of fishing operations
34-49 (62-91)	High to very high seas	Total suspension of fishing operations
50-63 (92-117)	Very high seas	Total suspension of fishing operations
≥ 64 (≥118)	Phenomenal	Total suspension of fishing operations



WEATHER WARNING GRAPHICS







- Action may be taken based on **ORANGE AND RED** COLOUR warnings.
- Vulnerable regions likely urban and hilly areas action may be initiated for heavy rainfall warning.
- As the lead period increases forecast accuracy decreases.




District-wise Heavy Rainfall for Tamil Nadu & Puducherry



Wind Warning Graphics



District-wise Warning Graphics for Andhra Pradesh & Yanam



Wind Warning




Wind warnings for Andhra Pradesh and Yanam.
Valid from 0830 hrs IST of 29.11.2025 to 0830 hrs IST of 30.11.2025

Date of Issue:- 29 November 2025

29 November 2025


Valid till 0830 hrs
IST of 2025.11.30



Wind warnings for Andhra Pradesh and Yanam.
Valid from 0830 hrs IST of 30.11.2025 to 0830 hrs IST of 01.12.2025

Date of Issue:- 29 November 2025


30 November 2025



Wind warnings for Andhra Pradesh and Yanam.
Valid from 0830 hrs IST of 01.12.2025 to 0830 hrs IST of 02.12.2025

Date of Issue:- 29 November 2025

01 December 2025



Flash Flood Guidance

24 hours Outlook for the Flash Flood Risk (FFR) till 2330 IST of 30-11-2025 :


Moderate flash flood risk likely over few watersheds & neighbourhoods of following Met Sub-divisions during next 24 hours.

Coastal Andhra Pradesh & Yanam - Nellore district. Rayalaseema - Chittoor and Kadapa districts.

Tamil Nadu - Puducherry & Karaikal - Cuddalore, Dharmapuri, Dindigul, Erode, Nilgiri, Salem, Teni and Tiruvallur districts.

Kerala & Mahe - Malappuram and Palakkad districts.

Surface runoff/ Inundation may occur at some fully saturated soils & low-lying areas over Area of Concern (AoC) as shown in map due to expected rainfall occurrence in next 24 hours.



Flash Flood Risk

High Risk (Take Action)

Moderate Risk (Be Prepared)


Low Risk (Be Updated)

Storm Surge Guidance






STORM SURGE HEIGHT INFORMATION:

* The below listed surge heights are over and above astronomical tide.

MANDAL/TALUK	DISTRICT	STATE / UNION TERRITORY	NEAREST PLACE OF HABITATION	STORM SURGE (m)	EXPECTED INUNDATION EXTENT (km)
Chengalpattu	Kancheepuram	Tamil Nadu	Muthukadu	0.3-0.5	Nil
Ponneri	Thiruvallur	Tamil Nadu	Karimanal	0.2-0.4	Upto 0.15



Fishermen Warning Graphics



Legend

Squally Weather with wind speed 35-45 kmph gusting to 55 kmph	Squally wind with speed 55-65 kmph gusting to 75 kmph
Squally Weather with wind speed 40-50 kmph gusting to 60 kmph	CS with Gale winds with speed 60-80 kmph gusting to 90 kmph
Squally Weather with wind speed 45-55 kmph gusting to 65 kmph	SCS with Gale wind speed 90-110 kmph gusting to 120 kmph
Squally wind with speed 45-55 kmph gusting to 65 kmph	VSCS with Gale wind speed 120-165 kmph gusting to 185 kmph
Squally wind with speed 50-60 kmph gusting to 70 kmph	ESCS with Gale wind speed 165-220 kmph gusting to 245 kmph

Fishermen are advised not to venture into the marked areas.